

**Name of work :- Providing Paver Block Paving near Oil Pipelines Outside Tank Termial (Phase-I)**

**SCHEDULE - B**

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Rate    |                 | Unit    |          | Amount (In Rs.) |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------|-----------------|---------|----------|-----------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          | In Fig. | In Words        | In Fig. | In Words |                 |
| 1       | Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 m :                                                                                                                                                                                                                                                                                                                                                                                       | 8236.00  |         |                 | M3      | Cum      |                 |
| 2       | Providing & Supply Quarry Spall with required Machinery for loading, Unloading of Material. Spreading Quarry Spall in Layers and Compact the layers with vibro rollers and watering. Machinery like Dumpers, Excavators, Loader, Grader, Vibro Roller etc. The work includes Royalty, Material, Machinery, Labour all complete as directed by engineer in charge                                                                                                                                                                                                                                                                                                                                                                                                      | 35580.00 |         |                 | M3      | Cum      |                 |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 5487.00  |         |                 | M3      | Cum      |                 |
| 4       | Providing and laying factory made chamfered edge Cement Concrete paver blocks In foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of course sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications : 80mm thick Cement concrete paver block of M-30 grade with approved colour, design & pattern. | 36580    |         |                 | M2      | SQM      |                 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |         |                 |         |          |                 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |         |                 |         |          |                 |
|         | <b>JE(C)</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |         | <b>XEN(PL )</b> |         |          |                 |