

Name of work :-CSR work for Construction of Hall / Dome for Indoor games at Shri Kutch Deshiya Sarswat Brahamn Mahasthan, Gandhidham.

SCHEDULE - B

Sr. No.	Description of Item	Quantity	Rate		Unit		Amount (In Rs.)
			In Fig.	In Words	In Fig.	In Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan), including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.50 m, as directed by Engineer-in-charge. All kinds of soil	120.00			M3	Cum	
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan), including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.50 m, as directed by Engineer-in-charge. Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil.						
	Column footing	48.00			M3	Cum	
3	Supplying and filling in plinth with sand under floors,including watering, ramming, consolidating and dressing complete. Plinth	154.79			M3	Cum	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	64.65			M3	Cum	
5	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering,shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge.“(Note :- Cement content considered in this item is @ 330 kg/cum.“Excess/ less cement used as per design mix is payable/recoverable						
a	All works upto plinth level	39.57			M3	Cum	
b	All works above plinth level upto floor V level	25.66			M3	Cum	
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth,	168.00			M3	Cum	
7	Thermo-Mechanically Treated bars of grade Fe-500D or more.Considering Average 130 kg /M3	8479.90			Kg	Per Kg	

Sr. No.	Description of Item	Quantity	Rate		Unit		Amount (In Rs.)
8	Centering and shuttering including strutting,propping etc. and removal of form for all heights Foundations, footings, bases of columns, etc. for mass concrete						
a	Sides of footing	40.80			M2	Sqm	
b	Columns, Pillars, Piers, Abutments, Posts and Struts	193.80			M2	Sqm	
c	Lintels, beams, plinth beams, girders, bressumers and cantilevers	248.19			M2	Sqm	
9	Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	225.00			M2	Sqm	
					Total Rs.		

Contractor

**Executive Engineer (CSR)
Deendayal Port Authority**