

BILL OF QUANTITY

Name of work: Reparining of approach road from NHAI road to Mithirihar GIDC via village road

T.I.No.	Description of item	Quantity	Rate		Unit		Amount
			In figures	In Words	In figures	In Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.						
a	All kinds of soil	4120.00			M3	One Cubic Metre	
2	Filling of approach road with quarry spall in layers of 200mm thick including cost of excavation royalty, taxes, loading, unloading, transportation spreading to required level, levelling, dressing in layers of 200mm each & wet consolidation by loaded trucks movement and at top with power vibratory roller 8 to 10 Tonne capacity etc. complete with all labour, material & equipment as directed by Engineer-in-Charge.	11330.00			M3	One Cubic Metre	
3	Collection, spreading, watering and consolidation of stone dust/stone grit by power vibratory roller of required capacity in a layer of average 20mm thickness to fill the voids of quarry spall layer surface including the cost of excavation Royalty, loading unloading and transportation at the site of work.	20600.00			M2	One Square metre	
						TOTAL	

Contractor**Superintending Engineer (Road)
Deendayal Port Authority**